

CHITALDROOG DIVISION.

ADVERTISEMENT.

The 31st May 1893.

Tenders are hereby invited for restoring the Sadaranahalu Tank in Holalkere Taluk.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 20th June 1893.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 200 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Items of Work.	Per.	Quantity.	Rate.
<i>Bund—</i>			
Earthwork	C. Yds.	62,378	
Grade stones with bottom slabs	Each.	37	
Index stones	Do	37	
B. M. stones	Do	2	
Register Number stone	Do	1	
Date stone	Do	1	
Gauge stone	Do	1	
Old stone work	C. Yds.	324	
New stone work	Do	4,836	
<i>Sluice—</i>			
Earthwork excavation	C. Yds.	236	
Brick in surki	C. Ft.	1,206	
Burnt slabs dressed	S. Ft.	300	
Gibbet stones with cross stones bed slabs top slabs and play fixed complete	L. S.	..	
Plastering	Sqr.	250	
<i>Waste Weir—</i>			
Clearing draft and excavation	C. Yds.	5,415	
Brick in chunam	C. Ft.	2,897	
Burnt stone slabs dressed	S. Ft.	984	
Plastering	Sqr.	482	
Rough stone work new	C. Yds.	781	
<i>Distribution—</i>			
For sluice	L. S.	..	

D. RANGA RAO,
Offg. Executive Engineer.